
Mangrove Creek Dam



Mangrove Creek Dam is an 80 metre high rockfill dam, with a concrete face, which stores water for the City of Gosford and Shire of Wyong. It is located approximately 50 kilometres north-west of Gosford, and provides on-stream storage of water, which is released upon demand to flow 20 kilometres downstream to the existing Mangrove Weir, from which water is pumped to Mooney and then to Gosford, via the treatment plant at Somersby.


The catchment area of 10,000 hectares, or 100 square kilometres, is typical sandstone eucalypt bush and is bounded by George Downes Drive to the east, the St Albans Road to the north and the Great North Road to the west. The Dam has a crest length of 380 metres. The storage capacity of the dam is approximately 190,000 megalitres (30% of the capacity of Sydney Harbour) and the stored waters have a surface area of approximately 700 hectares. Provision has been made in the current dam design for raising the dam a further 25 metres, thereby increasing the capacity to 420,000 megalitres (approximately equal to the volume of Sydney Harbour), with a stored water area of 1,200 hectares. Construction of this stage is projected to commence in approximately 20 years time.

The suitability of various types of dam was examined in the early stages of the investigation. A concrete dam was ruled out on the basis of high costs and unsuitability of the site. Construction of an earth or clay core dam was not practical because of the insufficient quantity of suitable core material available in the locality. A rockfill type dam with an impervious membrane on the upstream face appeared to be the best solution.

After comparing asphaltic concrete and reinforced concrete faced embankments, the latter type was selected as the most suitable, since the height of structure, the need for future raising of the dam, and cost comparisons all favoured this type.

The dam is composed basically of rolled, soft rockfill, utilising the Narrabeen Group of sandstones and siltstones, of which 1.3 million cubic metres was required. This material being obtained from a quarry located within the storage area. The embankment also contains approximately 100,000 cubic metres of processed basalt obtained from quarries at K ulnura and Peats Ridge. This material was incorporated into various filters and drains within the embankment to cope with seepage within the embankment and foundations. The concrete face which tapers from 600mm at the base to 300mm thick at the crest of the dam contains approximately 13,500 cubic metres of concrete and covers an area of approximately 30,000 square metres.

The Spillway is located on the left abutment and consists of a concrete lined channel, which varies in width from 20 metres to 10 metres. The channel is approximately 300 metres long, and will be used to carry overspill water when the dam is full. During construction, Mangrove Creek was being diverted through a tunnel in the left abutment. The tunnel is approximately half a kilometre long and 2.5 metres in diameter. A 50 metre high Intake Tower, in conjunction with valves located at the downstream end of the tunnel, facilitates the release of water from the dam into Mangrove Creek to supplement dry weather flows.



GOSFORD CITY COUNCIL

MANGROVE CREEK DAM

Data Sheet

Stage I

1. General

Type of Dam Concrete Faced Rockfill Full Supply Level RL 187.5m RL 152.5m Minimum Operating Level RL 193.2m Maximum Flood Level RL 194.5m Wave Wall Level RL 193.3m Crest Level 101 km₂ Catchment Area Average Annual Rainfall 1200mm 190,000 M1 Storage Capacity at FSL 680 Ha Surface Area Maximum Water Depth 65m

2. Embankment

Height of Dam (from lowest general foundation level to crest)

Length of Crest

Crest Width

Volume of Rockfill

80m

380m
6m
1,340,000m³

3. Spillway

Width 20m tapering to 10m
Length 240m

Type Concrete lined chute
Discharge Capacity 570m³/s
Energy Dissipation Flip Bucket

4. Intake Tower

Height 47m

Type Wet Well (Selective withdrawal by in line shutter system)

5. Outlet Works

Tunnel Lining Concrete and Mild Steel
Diameter 2.5m
Length 490m
Valves Two Butterfly Valves 2000 and 900mm diameter
Two Fixed Dispersion Cone Valves 1524 and 530mm diameter

6. Spillway Bridge

Length Width Type 20m
4.7m kerb to kerb
Single span composite
pretensioned girders/RC deck

7. <u>Intake Tower Bridge</u>

Length Width Type 60m
3.2m kerb to kerb
Two span composite steel
girder/RC deck

Stage I - Stage II comparison

	Stage 1	Stage I	
Storage Capacity at FSL	190,000	M1	455,000 Ml
Maximum Water Depth	65	m	90 m
Surface Area	680	Ha	1,360 Ha
Embankment Height	80	m	105 m
Crest Length	. 380	m	490 m
Volume of Rockfill	1,340,000	m ³	$2,740,000 \text{ m}^3$

LIST OF DAMS WHICH ARE EQUAL OR LARGER IN HEIGHT AND/OR CAPACITY WHEN COMPARED WITH MANGROVE CREEK DAM

NAME	HEIGHT	CAPACITY MEGALITRES*	AUTHORITY
Jindabyne	72 m	688,287	SMEC
Burrendong	76 m	1,188,000	SMEC
Glenbawn	78 m	360,000	WRC
Mangrove Creek Dam	80 m	190,000	GCC
Nepean	81 m	81,400	MWS&DB
Devils Gate	84 m	180,000	нес
Wyangla	85 m	1,220,000	WRC
Tumut Pond	86 m	52,793	SMEC
Upper Yarra	89 m	207,200	M B of W Vic
Gehi	91 m	21,043	SMEC
Blowerang	112 m	1,628,000	SMEC
Eucumbene	116 m	4,798,400	SMEC
Warragamba	137 m	2,091,800	MWS&DB

 $[\]star$ One megalitre is one million (1,000,000) litres which is approximately two hundred thousand (200,000) gallons